

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 14 AM 9:42

Josephine Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>K-12 W1/4 Cor</u>
	T _____ R _____	<u>Sec 36</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Clapp, in a field survey on November 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-12 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain 1/2 Mile Post 24" Beech is post	K-12 Recorded in Liber 2 Page 715, Jan 14, 1975 Fd Railroad Spike Power Pole NE 18.06' CL Hydrant NE 29.12' Power Pole SE 49.56' Power Pole SW 51.50'
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12
Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner
CL Hydrant AZ 26° 30.53'
Found Nail in NW Side Power Pole AZ 150° 49.57'
Found Nail in NE Side Power Pole AZ 221° 51.46'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 Cast Iron Monument in Monument Box SW Corner Brick Siding on Building #1157 SE Corner Conc. Step to Porch of House #1147 NE Corner Brick Bldg. NW Corner Brick Bldg.	AZ. 302° 58.08' AZ. 54° 60.73' AZ. 127° 150.61' AZ. 250° 157.23'
---	---

Signed by John P. Clapp
Surveyor's Michigan License No. 14091

Date Dec 5, 1994

