

SURVEY & REMONUMENTATION

APR 24 1995

Ottawa County Remonumentation LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:41

For corners in **COMMISSION**

Richard C. Coleman
REGISTER OF DEEDS
OF TAWA COUNTY, MI

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>K-13 SW Cor</u>
	T _____ R _____	<u>Sec 36</u>
	T _____ R _____	<u>Park Twp.</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John P. Clapp, in a field survey on November 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13 Govt Land Office Survey Notes 1832-Surveyor, Lucius Lyon Set Post 15" Beech N52 1/2 °E 21 links 24" Beech N41 °W 47 links	K-13 Recorded in Liber 4, Page 43 Mar 17, 1980 Fd Iron in Mon Box NW Cor Bk Gar S 92.33' CL Hydrant N35°E 53.16' SE Cor Hse N70°W 80.82' Power Pole S50°W 52.61'	K-13 Recorded in Liber 5 Page 309, Mar. 18, 1988 Iron in Mon. Box CL Hydrant NE 53.17' NW Cor St Hse SE 116.65' NW Cor Brk Gar S 92.33' SE Cor Blk Fnd NW 80.89' Iron W 75.05' Power Pole sW 52.61'
--	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13
Found iron pipe in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner
SE Corner House Foundation N65°W 80.85'
Allegan County Corner W 75.08'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Richard D. Nedewell


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13
Set O.C. Remon Iron and Cap in Monument Box
NE Corner House, Brick AZ.166°46' 95.07'
NW Corner House, Foundation AZ.247°09' 189.92'
SE Corner House, Foundation AZ.295°42' 80.85'
O.C. Remon Tag & Nail SE Side 18" Maple AZ. 54°53 159.77'
Allegan County Corner AZ.270°09'51" 75.08'

Signed by John P. Clapp

Date Dec 5, 1994

Surveyor's Michigan License No 14091



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983