

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 10:03

D. J. Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa
(County)

Located in:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|-------------------------------|
| 1. Public Land Survey | T <u>5N</u> R <u>16W</u> | <u>L-3 (N1/4 Cor. Sec 12)</u> |
| | T _____ R _____ | <u>Park Twp.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, John P. Clapp, in a field survey on November 29, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-3	L-3	L-3
Govt Land Office Survey Notes	Recorded in Liber 1,	Recorded in Liber 1,
1832-Surveyor, Calvin Britain	Page 15, May 4, 1971	Page 79, Sep 22, 1971
	Fd 1" Iron Pipe	Fd 1" Iron Pipe
9" Hemlock N25°E 17 links	46" Maple NNE 90.66'	46" Maple NNE 90.66'
10" Hemlock S25°W 18 links	10" Cherry NNW 118.63'	10" Cherry NNW 118.63'
	6" Cherry SE 84.62'	6" Cherry SE 84.62'
NOTE: Additional recordings	12" Oak SSE 111.88'	12" Oak SSE 111.88'
on reverse side Liber 5, Pg 148		

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


L-3		
Found cast iron monument in monument box (top missing) and accepted it as a careful and faithful perpetuation of the position of the original corner		
Found P.K. SW Side Power Pole	AZ 331°	53.25'
CL Street Sign	AZ 222°	42.83'
Found Nail in SW Side 12" Bl. Cherry	AZ 112°	85.22'

Madison D. Newell
P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3		
Found Cast Iron Monument in Monument Box (top missing)		
O.C. Remon Tag & Nail in NW Side 12" Twin Pine	AZ. 52°	178.95'
O.C. Remon Tag & Nail in SW Side 18" Oak	AZ. 141°	112.66'
O.C. Remon Tag & Nail NNW Side 5" Ornamental	AZ. 236°	60.17'
O.C. Remon Tag & Nail NE Side 10" Oak	AZ. 321°	85.83'



Signed by John P. Clapp Date Dec 2, 1994

Surveyor's Michigan License No. 14091

L-3

Recorded in Liber 5, Page 148

June 27, 1984

Found 1" Iron & Angle Iron

Set Cast Iron Monument

Power Pole	NW	53.45'
Street Sign	SW	42.90'
Twin 8" Maple	SE	70.77'
11" Cherry	ESE	85.26'

RECORDED
INDEXED
JUN 27 1984
FBI