

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 94 DEC 14 AM 10:03
Dorothy Robinson
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in
Ottawa

	(County)	Located In:		Corner Code #
		5N	16W	
1. Public Land Survey		T	R	L-5 N1/4 Cor Sec 13 Park Twp.
		T	R	
		T	R	
		T	R	
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	
4. Lot No. _____, Recorded Plat _____				
5. Private Claims _____				

Register of Deeds Stamp & File Number

John P. Clapp

November 21 94

I, John P. Clapp, in a field survey on November 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-5 Govt Land Office Survey Notes
 1832-Surveyor, Calvin Britain
 Set Post
 10" Hemlock S45°E 21 links
 8" Hemlock N3°W 21 links
 See reverse side for additional recordings (Liber 5, Page 275)

Recorded in Liber 2
 Page 822 Oct 20, 1975
 Angle Iron
 Power Pole S 47.02'
 Conc. Mon. S 33.00'
 NW Cor Hse. SSE 80.21'
 NE Gar Cor N 117.58'
 CL Road N 3.4'

L-5 Recorded in Liber 5
 Page 141, June 27, 1984
 Found Angle Iron
 Set Cast Iron Monument
 NW Cor Hse SSE 80.22'
 Hydrant N 30.34
 Power Pole S 47.54'
 14" Poplar SW 94.62'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5
 Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner
 Found P.K. in W Side Power Pole AZ 181° 47.53'
 NW Corner House AZ 169° 80.32'
 Hydrant AZ 5° 35.57'

Michael P. Peterson
 P.A. 345 OTTAWA COUNTY


PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5
 Cast Iron Monument in Monument Box
 O.C. Remon Tag & Nail SW Side Power Pole AZ. 306° 47.71'
 NW Garage Corner on House #14808 AZ. 231° 131.70'
 SW Corner House AZ. 54° 186.09'
 NE Corner Concrete Porch of House #14796 AZ. 141° 97.46'

Signed by John P. Clapp *John P. Clapp* Date Dec 5, 1994

Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

L-5

Recorded in Liber 5, Page 275

August 17, 1987

Found Cast Iron Monument

NW Corner House	SSE	80.22'
Hydrant	N	30.34'
Power Pole	S	47.54'
14" Poplar	SW	94.62'

CODE #
CORNER
CODE #
NCSN