

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 10:02

COMMISSION

For corners in

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>L-7 N1/4 Cor</u>
	T _____ R _____	<u>Sec. 24</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Clapp, in a field survey on November 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-7 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain Set 1/4 Sec Post on True Line 14" Hemlock N31°W 12 links 20" Red Oak S75°E 33 links See reverse side for additional recordings Liber 6, Page 173 Liber 6, Page 202	L-7 Recorded in Liber 2 Page 227, June 25, 1973 Fd Steel Bar in Monument Box Power Pole NW 26.10' 24" Oak SE 67.82' 10" Oak NE 94.38'	L-7 Recorded in Liber 3 Page 356, Jun 28, 1979 Found angle iron T Pole SW 88.70' T Pole NE 58.24' 20" Maple SE 42.30' 18" Tw Oak NE 65.74'
--	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7
Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner

CL Hydrant	AZ 42°	50.03'
Nail in N Side 36" Oak	AZ 121°	68.31'
P.K. in N Side Power Pole	AZ 108°	110.42'
P.K. Nail in NW Side 14" Pine	AZ 49°	79.23'

Richard P. Nedwell
P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7
Cast Iron in Monument in Monument Box

O.C. Remon Tag & Nail NW Side 14" Pine	AZ. 49°	79.31'
O.C. Remon Tag & Nail NNE Side 36" Oak	AZ. 121°	69.27'
O.C. Remon Tag & Nail W Side 15" Tw Cherry	AZ. 192°	182.57'
O.C. Remon Tag & Nail SW Side 18" Spruce	AZ. 306°	55.96'

Signed by John P. Clapp *John P. Clapp* Date Dec. 5, 1994
Surveyor's Michigan License No. 1409



