

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
94 DEC 14 AM 9:41

Philip D. Hedwood
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>L-13 S1/4 Cor.</u>
	T _____ R _____	<u>Sec. 36</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John P. Clapp, in a field survey on November 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13
Govt Land Office Survey Notes
1832-Surveyor, Lucius Lyon
Set Post
15" Beech N42 °E 21 links
22" Beech N31 °W 48 links

L-13
Recorded in Liber 3,
Page 160, Mar. 16, 1977
Boat Spike in Mon Box
SE Cor School Building NW 82.83'
Power Pole NE 53.45'
NE Cor Porch Foundation SE 85.68'
CL Mon Box for Allegan County W 34.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13
Found steel bar in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner
SE Corner Brick School NW 82.77'
NE Corner Porch Foundation SE 85.67'
Allegan County Corner W 34.40'


P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Philip D. Hedwood

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13
Set O.C. Remon Iron and Cap in Monument Box
SW Corner House, Brick AZ. 41°24' 112.76'
SE Corner School, Brick AZ. 315°04' 82.77'
NE Corner Porch Foundation AZ. 150°24' 85.67'
SE Corner House, Brick AZ. 50°08' 131.95'
Allegan County Corner AZ. 270°00'33" 34.40'

Signed by John P. Clapp
Surveyor's Michigan License No. 14091

Date Dec 5, 1994



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, REVISED MAY 14, 1975
REGISTERED LAND SURVEYOR, JAN., 1983