

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

96 DEC 14 AM 9:41

*D. J. ...*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>M-3 (NE Cor Sec 12)</u> <u>Park Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John P. Clapp, in a field survey on November 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

<b>M-3</b>	<b>M-3 Recorded in Liber 1, Pg 75</b>	<b>M-3</b>
Govt Land Office Survey Notes	Sept 22, 1971 Fd Boat Spike	Recorded in Liber 5,
1832-Surveyor, Calvin Britain	Tele. Pole SW 55.84'	Page 148, June 27, 1984
10" Aspen N52°W 1.89 ch	St Sign SW 41.20'	Fd Spike over iron pipe
10" Aspen S29°W 2.23 ch	Tele. Pole NE 82.73'	Set cast iron monument
	20" Maple NE 70.15'	Power Pole SW 50.50'
	Tele Pole SE 124.96'	26" Maple NE 70.24'
	SE Cor Gar NW 108.09'	Light Pole NW 44.67'
	Holland Cor N 25.68'	Holland Cor N 25.64'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**M-3**  
Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner


CL Street Sign	AZ 215°	45.35'
Found Nail SW Side 30" Maple	AZ 58°	70.18'
SE Cor Attached Garage	AZ 312°	108.09'
Holland Twp Corner	N	25.69'
Nail & Tag SE Side Power Pole	AZ 210°	50.51'
P.K. SE Side Light Pole	AZ 332°	44.88'

*Wendy P. Newbold*  
**P.A. 345 OTTAWA COUNTY**  
**PEER APPROVED** 12/12/94

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**M-3**  
Found Cast Iron Monument in Monument Box

O.C. Remon Tag & Nail NW Side 30" Maple	AZ.	58°	71.22'
"X" NE End 18" Concrete Culvert	AZ.	126°	50.42'
O.C. Remon Tag & Nail SE Side Power Pole	AZ.	210°	50.54'
O.C. Remon Tag & Nail NE Side 12" Quad Maple	AZ.	309°	71.40'
Holland Township Corner	N		25.69'



Signed by John P. Clapp Date Dec. 2, 1994  
Surveyor's Michigan License No. 14091