

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 10:02

Register of Deeds
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>M-4 E1/4 Cor.</u>
	T _____ R _____	<u>See 12</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Clapp, in a field survey on November 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-4 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain Set Post 10" Pine N49 °W 24 links 10" Aspen S15 °W 93 links See reverse side for additional recordings (Liber 5, Page 274)	M-4 Recorded in Liber 3 Page 342, Feb 28, 1979 Found "T" Iron Holland Cor N 29.12' 20" Oak E 101.44' Power Pole SSW 173.43 Pipeline Sign E 25.35'	M-4 Recorded in Liber 5 Page 114, June 27, 1984 Fd "T" Iron Set C.I.M. Holland Cor N 29.13' Power Pole NW 190.50' Pipeline Sign NW 58.42' 22" Maple E 100.92'
--	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


M-4 Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner Holland Township Corner Found Nail & Tag S Side 24" Oak CL Pipeline Test Lead Station CL Pipeline Sign Found Nail & Tag E Side Power Pole	AZ. 0° 29.13' AZ 78° 101.40' AZ 79° 25.65' AZ 330° 58.64' AZ 182° 173.44'	<i>John P. Clapp</i> P.A. 345 OTTAWA COUNTY PEER APPROVED <u>12/12/94</u>
---	---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 Cast Iron Monument in Monument Box O.C. Remon Tag & Nail N Side 24" Oak "X" in S End Concrete Culvert O.C. Remon Tag & Nail SW Side 9" Pine Holland Twp Corner (C.I.M.)	AZ. 78° 101.06' AZ. 195° 54.74' AZ. 131° 79.55' AZ. 0° 29.13'
---	--

Signed by John P. Clapp Date Dec. 5, 1994

Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS MAY 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

M-4

Recorded in Liber 5, Page 274

August 17, 1987

Cast Iron Monument

Holland Corner	N	29.13'
Power Pole	NW	190.50'
Pipeline Sign	NW	58.42'
22" Maple	E	100.92'

CODE #
OWNER
DATE #
1987