

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 14 AM 10:03

Dorothy Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>M-5 NE Cor</u>
	T _____ R _____	<u>Sec 13</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

John P. Clapp, in a field survey on November 21, 19 94,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

M-5 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain 10" Beech is post See reverse side for additional recordings (Liber 5, Page 367)	M-5 Rec. in Liber 3 Page 27, Jan 14, 1976 Found Iron Pipe Power Pole NE 35.10' St. Sign SE 41.84' Guy Pole SW 35.10' P/L Marker NW 40.85'	M-5 Rec. Liber 3 Page 342, Feb 28, 1979 Found Iron Pipe Power Pole NE 35.10' Street Sign SE 41.84' Guy Pole SW 35.10' PL Marker NW 40.85' Holland Cor N 32.50'
-----------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5
Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner

P/L Marker	AZ 300°	41.06'
Holland Township Marker	N	32.48'
SW Corner House Foundation	AZ 53°	120.10'
SW Corner House Foundation	AZ 156°	120.77'
Found Nail & Tag SE Side Power Pole	AZ 49°	35.06'
CL Pipeline Test Lead Station	AZ 233°	43.82'

Madison D. Newbold
P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94


Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5
Cast Iron Monument in Monument Box

SW Corner House Foundation	AZ. 305°	103.38'
SE Corner Concrete Porch	AZ. 213°	108.86'
SW Corner House Foundation	AZ. 53°	120.10'
SW Corner House Foundation	AZ. 156°	120.77'

signed by John P. Clapp *John P. Clapp* Date Dec 5, 1994

Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

M-5
Recorded in Liber 5,
Page 367, June 23, 1989
Set Cast Iron Monument

Holland Corner	N	32.46'
Power Pole	NE	35.07'
38" Maple	NW	71.72'
28" Maple	SE	82.78'
Pipeline Marker	SW	43.80'

1989
CORNER # 2000
CORNER # 2000
CORNER # 2000

1989
CORNER # 2000
CORNER # 2000