

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

For corners in

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:42

*Phyllis K. Korman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Ottawa (County) Located In: Corner Code #

1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>M-6 E 1/4 Cor</u>
	T _____ R _____	<u>Sec 13</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Clapp, in a field survey on November 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<b>M-6</b> Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain Set 1/2 Mile Post 8" Beech is Post	<b>M-6</b> Recorded in Liber 5 Page 112 June 27, 1984 Fd Iron Pipe, Set CIM Holland Cor N 18.16' Power Pole ENE 29.92' 17" Beech SE 92.05' 13" Oak WSW 61.28'	<b>M-6</b> Recorded in Liber 5 Page 154, Oct 29, 1984 Set Cast Iron Monument Holland Cor N 18.18' Tw 12" Oak E 57.92' 15" Oak WSW 61.10' 4" Poplar WNW 61.54'
---	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<b>M-6</b> Found cast iron monument in concrete in pavement and accepted it as a careful and faithful perpetuation of the position of the original corner Holland Township Corner N 18.18' CL Hydrant AZ 44° 45.83' NW Cor Porch Foundation AZ 115° 77.80'
--


P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

*Robert P. Medowald*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<b>M-6</b> Found Cast Iron Monument in Concrete in Pavement O.C. Remon Tag & Nail SW Side 18" Beech AZ. 148° 92.22' NW Corner Garage Foundation AZ. 229° 140.69' O.C. Remon Tag & Nail SW Side 12" Pine AZ. 317° 78.52' O.C. Remon Tag & Nail NW Side 14" Pine AZ. 55° 100.48'
---



Signed by John P. Clapp Date Dec. 5, 1994

Surveyor's Michigan License No. 14091

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1993