

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 10:03

Deborah A. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>5N 16W</u>	<u>M-7 SE Cor Sec 13</u>
	T <u> </u>	<u>Park Twp.</u>
	T <u> </u>	<u> </u>
	T <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u>	<u> </u>
	S <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u>	<u> </u>
	S <u> </u>	<u> </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John P. Clapp in a field survey on November 28, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7 Govt Land Office Survey Notes Page 227, June 25, 1973 1832-Surveyor, Calvin Britain Post 18" Beech N50°W 6 links 10" Beech S30°W 26 links (see reverse side for additional recordings Liber 4, Page 186)	M-7 Recorded in Liber 2 Fd Angle Iron CL Pipe Vent NW 57.01' T. Pole S75°W88.70' CL Pipe Vent NE 56.72' 20" Maple SE 42.30' 18" Tw Oak NE 65.74' T. Pole NE 58.24'	M-7 Recorded in Liber 3, Page 356, June 29, 1979 Fd 1/2" Rod Mon. Box P. Pole NW 26.10' 24" Oak SE 67.82' 10" Oak NE 94.38'
--	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7
Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner

CL Hydrant	AZ 40°	75.16'
SE Cor Garage Foundation	AZ 310°	115.53'
Found Nail & Tag NW Side 10" Pine	AZ 239°	68.39'
Holland Twp. Corner	AZ 1°	28.20'


Deborah P. Robinson
REG. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7
Cast Iron Monument in Monument Box

O.C. Remon Nail & Tag NE Side 28" Oak	AZ. 155°	42.04'
O.C. Remon Nail & Tag SE Side 10" White Pine	AZ. 239°	68.31'
O.C. Remon Nail & Tag NW Side 26" Oak	AZ. 33°	98.80'
SE Corner Garage Foundation	AZ. 310°	115.53'
Holland Township Corner	AZ. 1°	28.20'

Signed by John P. Clapp *John P. Clapp* Date Dec 2, 1994
Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, MAY 14, 1975
REVISED JAN., 1983

M-7
 Recorded in Liber 4
 Page 186, May 13, 1981
 Found Angle Iron, Set 1/2" Rod
 5" Pine SW 52.28'
 6" Oak NW 88.34'
 Tw 20" Oak NE 66.32'
 24" Oak SE 40.89'

M-7
 Recorded in Liber 5
 Page 112, *Jun. 27, 1984*
 Found Iron Bar, Set CIM
 Power Pole NE 58.48'
 28" Maple SE 41.24'
 Light Pole WSW 89.68'
 Holland Twp
 Corner N 28.20'

M-7
 Recorded in Liber 6
 Page 202, Jan 30, 1992
 SE Cor C. Gar NW 115.50'
 Top Hyd. NE 75.12'
 10" Pine SW 68.37'
 38" Oak SE 41.54'

1984
 JUN 27 1984
 1992
 JAN 30 1992