

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
94 DEC 14 AM 10:03

Richard L. Anderson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>M-8 (E1/4 Cor Sec 24)</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Clapp, in a field survey on November 28, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain Set 1/2 Mile Post 10" Hemlock is post (See reverse side for additional recordings Liber 6, Page 203)	M-8 Recorded in Liber 4 Page 185, May 19, 1981 Found 3/4" Iron Pipe from Witnesses Power Pole SW 35.10' Power Pole NW 40.13' Power Pole NNE 63.18' Power Pole NE 81.43'	M-8 Recorded in Liber 6 Page 185, Nov 6, 1991 Fd Iron in Monument Box Set Cast Iron Monument Holland Cor N 13.91' Power Pole NE 63.10' Power Pole NW 40.06' 18" Oak SE 83.23'
--	---	--

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner		
Found Nail & Tag in SE Side Power Pole	AZ 36°	63.03'
Found Nail & Tag in S Side 30" Oak	AZ 26°	83.06'
Found P.K. in SE Side Power Pole	AZ 321°	40.04'
Found Nail & Tag in NE Side 18" Oak	AZ 136°	83.17'

Madison D. Newell
P.A. 345 OTTAWA COUNTY


PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 Cast Iron Monument in Monument Box		
O.C. Remon Tag & Nail NW Side 30" Oak	AZ. 26°	83.95'
O.C. Remon Tag & Nail NE Side Power Pole	AZ. 321°	40.15'
O.C. Remon Tag & Nail E Side Power Pole	AZ. 191°	121.89'
O.C. Remon Tag & Nail NE Side 18" Oak	AZ. 136°	83.16'

Signed by John P. Clapp *John P. Clapp*
Surveyor's Michigan License No. 1409

Date Dec 2, 1994



M-8
Recorded in Liber 6, Page 203
March 11, 1992
Cast Iron Monument in Monument Box
Power Pole NW 40.04'
Top Hydrant NE 71.07'
16" Oak SE 83.15'
Holland Cor N 14'

1992
2000
2000
2000