

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:42

Richard R. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>M-9 NE Cor</u>
	T _____ R _____	<u>Sec 25</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Clapp, in a field survey on November 21, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-9 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain Set Post	M-9 Recorded in Liber 1 Page 387, May 11, 1972 Found Iron Pipe from Old County Ties
18" Pine N37°W 30 links	NE House Corner SW 99.68'
18" Pine S85°W 17 links	Pipeline Vent NW 47.30'
	Power Pole W 26.93'
	Guy Pole NE 45.62'
	Support Pole SE 63.73'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9
Found iron pipe in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner
Found P.K. Nail in S. Side Power Pole AZ 279° 27.66'


Maday D. Hedwell PA. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Set O.C. Remon cap & bar in concrete in monument box		
O.C. Remon Nail & Tag S Side Power Pole	AZ. 279°	27.53'
O.C. Remon Nail & Tag NW Side Blue Spruce	AZ. 226°	93.42'
O.C. Remon Nail & Tag SW Side Oak	AZ. 94°	28.16'
O.C. Remon Nail & Tag S Side Power Pole	AZ. 147°	104.77'

Signed by John P. Clapp *John P. Clapp*
Surveyor's Michigan License No. 14091

Date Dec 5, 1994



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983