

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 10:02

Phyllis Johnson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Sequence # 1

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>M-10 (E1/4 Cor Sec 25)</u>
	T _____ R _____	<u>Park Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John P. Clapp, in a field survey on November 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10 Gov't Land Office Survey Notes 1832 - Surveyor, Calvin Britain Set 1/2 Mile Post 12" White Oak N20°W 11links 12" White Oak S40°W 20 links	M-10 Recorded in Liber 6, Page 265 Sept. 20, 1993 Set CIM (fits plats on all sides of intersection) (No Twp. jog) NE Corner House SE 111.60' SW Corner House NE 106.70' SE Corner Porch Fnd NW 86.25' NE Corner House SW 105.23'
---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10
Found cast iron monument flush with pavement and accepted it as a careful and faithful perpetuation of the position of the original corner

NE Corner House Foundation	AZ 122°	111.60
SW Corner House #189	AZ 57°	106.70'
SE Corner Porch Foundation	AZ 317°	86.25'
NE Corner House	AZ 241°	105.23'


Richard P. Newbold
P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10
Found Cast Iron Monument

O.C. Remon tag & nail in NW Side 22" Maple	AZ. 53°	83.47'
O.C. Remon tag & nail in W Side 36" Oak	AZ. 153°	47.21'
O.C. Remon tag & nail in SE Side 15" Oak	AZ. 223°	47.26'
SW Corner House Foundation House #679	AZ. 301°	108.85'



Signed by John P. Clapp Date Dec. 2, 1994

Surveyor's Michigan License No. 14091