

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 14 AM 9:41

Register of Deeds
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>16W</u>	<u>M-13 SE Cor</u>
	T _____ R _____	<u>See 35</u>
	T _____ R _____	<u>Park Twp.</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John P. Clapp, in a field survey on November 30 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13 Govt Land Office Survey Notes 1832-Surveyor, Lucius Lyon Set Corner Post 6" Beech N59°E 53 links Hemlock S31°W 25 links	M-13 Recorded in Liber 3, Pg 61 March 22, 1976 in Allegan Co. Iron Found in Monument Box Nail side P. Pole SE 39.91' CL Hydrant NE 44.49' Nail side Guy Pole NW 37.99'	M-13 Recorded in Liber 2, Page 377 Mar. 27, 1975 in Allegan Co. Nail & Cap Guy Pole NW 38.00' PK NE Side P. Pole SE 39.90' SW Cor 12x12 Conc NE 45.70' Cor Fence Post
--	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13
Found iron in monument box and accepted it as a careful and faithful perpetuation of the original corner.
Nail in Side of Power Pole SE 39.91'
CL Hydrant NE 44.99'


P.A. 345 OTTAWA COUNTY
DEED APPROVED 12/12/94

Maday D. Nedawala

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 Replaced iron in monument box with O.C. Remonumentation Iron & Cap		
O.C. Remon Tag & Nail NW Side 18" Pine	AZ. 49°	137.78'
O.C. Remon Tag & Nail N Side 12" Pine	AZ. 112°	103.00'
O.C. Remon Tag & Nail S Side 16" Maple	AZ. 245°	98.83'
O.C. Remon Tag & Nail NE Side 14" Maple	AZ. 310°	75.70'
O.C. Remon Tag & Nail S Side 14" Pine	AZ. 70°	148.39'
O.C. Remon Tag & Nail E Side 12" Oak	AZ. 136°	104.10'

Signed by John P. Clapp Date Dec 5, 1994
Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983