

SURVEY & REMONUMENTATION

DEC 01 1998

SECTION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 98 MAY 22 PM 4:06

For corners in

| | | |
|---------------------------------------|--------------------------|---|
| <u>Ottawa</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>6N</u> R <u>13W</u> | <u>A-7 (NW, 19)</u> <u>Georgetown Twp.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

[Signature]
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on March 12, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | |
|--------------------------------|----------------------------|-----------------------------|
| A-7 | LCRC L3, P80, April, 1976 | LCRC L1, P728, Nov., 1972 |
| Lucius Lyon, 1831 | St. sign S 85 E 65.23' | 3/4" solid iron in mon. box |
| West Boundary 20 South of post | PP S 85 E 60.23' | PP S 87 E 60.35' |
| Set post cor. Secs. 18 & 19 | NW cor. hse. footing | 38" Oak N 25 W 71.55' |
| Pine 28 N 38 E 22 | S 41 E 161.97' | S end culvt. S 70 W 53.70' |
| Bech 6 S 13 E 38 | S end culvt. S 76 W 53.60' | |
| | TP N 40 W 71.75' | |
| | 28" Oak N 30 W 71.65' | OVER |
| | Blendon cor. 13.17' | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 Found 4" Harrison Mon. in Mon., Mon. is 0.10' East of East Line of Twp.
 M-7 (NE, 24) & M-8 (E 1/4, 24) 6-14

As per above wit. & wit. on back

And is accepted as a careful and faithful perpetuation of the position of the original corner.

PA. 345 OTTAWA COUNTY
PEER APPROVED 4/20/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 4" Harrison Mon. in Mon. Box Wit. are to point on Twp. Line
 Ottawa Co. Remon. Tag & Nail in S side UP S 45° W 51.34'
 Ottawa Co. Remon. Tag & Nail in S side UP S 85° E 60.43'
 Ottawa Co. Remon. Tag & Nail in SW side 38" Oak N 20° W 71.32'
 Ottawa Co. Remon. Tag & Nail in W side 10" Oak N 55° W 91.54'
 Top of hydr. N 20° E 63.37'
 Blendon cor. M-7 North 13.25'
 On C/L bit. N-S; on C/L bit. West & tree row East



* \$11.00 CORNER
 * \$2.00 PHOTO

Signed by John C. Bueche
 John C. Bueche, P.S.
 Surveyor's Michigan License No. 13027

Date 3-13-98

SURVEY &
REMONUMENTATION

DEC 01 1998

PART A - continued

SECTION

LCRC L5, P118, June, 1984
Fnd. 1/2" iron bar in MB set CIM
PP E 60.33'
8" Pine NE 51.45'
30" Oak NNW 71.49'
TP NW 71.72'

Exxel, 1992 notes
CI Mon. in Mon. Box
PK in N side PP E 60.33'
PK in SE side PP SW 51.36'
Nail in SW side 20" Maple SE 88.77'
Nail in SW side 36" Oak NW 71.48'
Cor. for Sec. to W, N 13.25'

