

FEB 18 1994

COMMISSION

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV -8 PM 1:58

*Randy D. Feenstra*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 13W	A-11, NW cor Sec. 31, Geotwn
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randal D. Feenstra in a field survey on July 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-11 = L.C.R.C.# 's

L-4, P-146 Iron in box	L-5, P-92 C.I. Mon.	L-6, P-217 C.I. Mon. in box
P.K. on P. Pole SE 45.4'	30" oak SSW 85.60'	P.K. in P. Pole S47°W 52.90'
P.K. on P. Pole SW 53.3'	P. Pole SW 53.25'	Nail in 40" oak S85°W 85.47'
Blendon Cor. S 4.00'	P. Pole SE 45.33'	Blendon Monument S 4.00'
	Blendon Cor. S 4.00'	P.K. in P. Pole S38°E 45.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11 Found cast iron monument - accepted as a careful and faithful perpetuation of the position of the original corner.

P.K. Nail in P. Pole	S47°W	52.90'
Nail in 40" oak	S85°W	85.47'
Blendon Cor.	S	4.00'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 Ottawa County Monument

O.C. Remon. Nail & Tag in P. Pole	S45°W	53.17'
O.C. Remon. Nail & Tag in P. Pole	S40°E	56.82'
O.C. Remon. Nail & Tag in 30" Oak	S80°W	85.02'
CL Hydrant	N35°E	47.30'
Blendon Corner	S0°E	4.0'
On CL 48th, 2' North of CL Van Buren		



Signed by *Randal D. Feenstra* Date Sept 29; 1993  
Surveyor's Michigan License No. 37275