

FEB 16 1994

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Randy D. Feenstra
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in **COMMISSION**

<u>Ottawa</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>6N</u> R <u>13W</u>	A-12, WI/4 COR Sec. 31, Geotwn.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Randal D. Feenstra, in a field survey on Sept. 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


A-12 L.C.R.C. # L-6, P-218 - "T" Iron
 P.K. in P.Pole S25°W 77.65'
 Nail in 52" Maple S25°E 55.50'
 Nail in 52" Maple S10°E 109.50'
 SE Cor, Conc. Fnd. to garage N40°W 88.10
 CL N-S Road - W 1.0±
 Blendon Cor. S 11.25'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12 Found "T" Iron - accepted as a careful and faithful perpetuation of the position of original corner.
 Found Blendon Cor. S 11.45'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12 Set O.C. Remon. Rod and Cap in Concrete
 O.C. Remon. Nail & Tag in P.Pole S35°W 83.29'
 O.C. Remon. Nail & Tag in P.Pole S10°E 78.56'
 O.C. Remon. Nail & Tag in Twin 30" Maple N75°W 120.54'
 SE Cor. Conc. Fnd'n to Garage N50°W 88.01'
 Blendon Cor. S0°E 11.45'
 On CL 48th



Signed by *Randal D. Feenstra* Date Sept 29; 1993

Surveyor's Michigan License No. 37275