

1993

OTTAWA COUNTY REMONUMENTATION

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

93 DEC 15 AM 9:26

Filing Requirement of Act 74, Mich. P.A. 1970

Daphne R. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in OTTAWA

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|-----|----------------|
| 1. Public Land Survey | T | 6N | R | 13W | C-5 (SE cor |
| | T | | R | | Section 7) |
| | T | | R | | Georgetown Twp |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal J. Vugteveen in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-5 LCRC Liber 1, Page 603		C-5 LCRC Liber 2, Page 593
Nail in side cor fence post SSE 1.20 /		Found 1" Iron Bar
Nail in side fence post N 57.61 / Nail in		Fence post N 1.18'
side 8" Oak ENE 69.65		Cor fence post SE 0.72'
		Fence post SSE 10.05'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5 Found CIM tree ROW N & E & S and accepted as a careful and faithful perpetuation of the position of the original corner		
Nail in side cor fence post SSE 1.71		Fence post N 1.18' laying down
leaning South		Cor fence post SE 0.72' leaning South
Center 12" Oak ENE 69.5'		Fence post SSE 10.05' laying down
		Found PK in W side 8" Elm N 43.18'
		Found N&T in W side 6" Elm S3W 15.22'
		Found N&T in S side 10" Elm N45E 9.71'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5 Cast Iron Monument


Set Ottawa County Remon Tag & Nail in N side Triple 12" Oak NE 69.58'

Set Ottawa County Remon Tag & nail in W side 8" Elm N 43.18'

Set Ottawa County Remon Tag & Nail in corner fence post SSE 1.41'

Set Ottawa County Remon Tag & Nail in W side 6" Elm S3W 15.22'

Set Ottawa County Remon Tag & Nail in S side 10" Elm N45E 9.71'



Signed by *Randal J. Vugteveen* Date Dec 6, 1993

Surveyor's Michigan License No. 28429