

SURVEY & REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
OTTAWA
(County)

Located In: Corner Code #
 T6N R13W D-3 (S 1/4 cor
 Section 5)
 Georgetown Twp.

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

RECORDED

95 NOV 15 PM 2:10

Phyllis Carlsson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3		●										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randal J. Vugteveen, in a field survey on October 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-3 Common corner to Sections 5 & 8

1831 - Sibley	Liber 2, Page 13	Liber 2, Page 209
Set post	Found steel bar	Nail in 30" Oak NW 59.62'
Sugar N42 W10 7 Links	P. pole SE 104.45'	Nail in P pole SE 104.78'
Beech S18 E 17 8 Links	20" Maple W 29.50'	Nail in 18" Oak W 30.27'
	36" oak NW 58.45'	
	C/L st. sign SE 45.70'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-3 Found 5/8 solid bar in mon box on centerline 36th Ave & centerline Taylor St. East and accepted as a careful and faithful perpetuation of the position of the original corner
 Nail & Tag in NW side p. pole AZ 136 deg 104.47'
 Nail & Tag in SW side 36" Oak 59.5'
 Centerline Street sign SE 45.65'


P.A. 345 OTTAWA COUNTY
 PEER APPROVED 10/23/95

Peer Approved
Randal J. Vugteveen

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-3 Removed 5/8" bar, set 3/4" X 24" solid bar with Ottawa County Remon Cap in mon box

Set Ottawa County Remon Nail & Tag in N side Triple 6" Hickory AZ. 263 deg 32.78'
 Set Ottawa County Remon Nail & Tag in SW side 36" Oak AZ. 327 deg 59.56'
 Set Ottawa County Remon Nail & Tag in NE side p. pole AZ. 136 deg 104.85'
 Set Ottawa County Remon Nail & Tag in SE side p. pole AZ. 17 deg 247.38'
 Found "T" iron Az. 270 deg 33.01'



Signed by Randal J. Vugteveen
 Surveyor's Michigan License No. 28429

Date Oct. 20, 1995