

1993

OTTAWA COUNTY REMONUMENTATION

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 15 AM 9:26

For corners in OTTAWA

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>13W</u>	D-5 (S 1/4 cor Section 8) Georgetown Twp
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randal J. Vugteveen, in a field survey on Nov 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5 LCRC Liber 2, Page 593	D-5 LCRC Liber 5, Page 255
Found R.R. Spike	Set CIM
Tel. Pole E 27.24'	TP E 27.87'
16" Ash SSW 72.15'	27" Maple SE 78.74'
18" Hickory W 31.15'	Twin 15" Hic. W 31.76'
SW cor of hse SE 89.25'	33" Chestnut SSW 72.43'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 Found broken CIM in mon box on centerline of 36th Street and accepted as a careful and faithful perpetuation of the position of the original corner	
16" Ash SSW 72.35'	TP E 27.91'
18" Hickory W 31.70'	27" Maple SE 78.74'
SW cor of porch SE 76.20'	33" Chestnut SSW 72.35'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 Cast Iron Monument

Set Ottawa County Remon Tag & Nail S side TP E 27.91'

Set Ottawa County Remon Tag & Nail N side 15" Twin Hickory S85W 31.70'

SE fnd cor hse #8025 N58W 94.94'

Set Ottawa County Remon Tag & Nail in NW side 24" Basswood S22W 72.35'

SW brk cor garage #8024 N72E 176.17'



Signed by Randal J. Vugteveen

Date Dec 6, 1993

Surveyor's Michigan License No. 28429