

1233

OTTAWA COUNTY REMONUMENTATION

RECORDED

LAND CORNER RECORDATION CERTIFICATE

93 DEC 15 AM 9:26

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in OTTAWA

(County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 13W	E-6 (E 1/4 cor Section 17) Georgetown Twp
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randal J. Vugteveen, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


E-6 LCRC Liber 1, Page 481	E-6 LCRC Liber 1, Page 743	E-6 LCRC Liber 5, Page 255
1/2" Iron Pipe	Nail in side T. pole N 63.70' / Spike in	Set CIM
NW cor hse 2' above ground S12E 90.00' /	side 12" Maple NNE 39.04' / SW cor gar NW	15" Chestnut N 34.29'
Nail in face 12" Maple N40E 38.46' / Nail	166.62' / NE cor hse foundation SE 114.13'	15" Maple NE 39.36'
in face 10" Ash N 33.82' / Nail in face		9" Tree SE 36.06'
MBT pole N06W 63.40'		8" Chestnut SW 50.68'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 Found broken mon in mon box 3' N of centerline Baldwin and 33' West of centerline Park Ridge Drive and accepted as a careful and faithful perpetuation of the position of the original corner		
NW cor hse 2' above ground S12E 90.18'	SW cor gar NW 166.62'	9" Tree SE 36.06'
	NE cor hse foundation SE 114.13'	8" Chestnut SW 50.63'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 Cast Iron Monument
Set Ottawa County Remon Tag & Nail in E side 12" Maple N 49.05'
Set Ottawa County Remon Tag & Nail in W side 12' Tree S20E 36.02'
Set Ottawa County Remon Tag & Nail in NW side 9" Chestnut S44W 50.63'
Set Ottawa County Remon Tag & nail in S side 48" Maple N75E 138.06'
NW fnd corner hse #3190 S13E 90.18'



Signed by Randal J. Vugteveen Date Dec 6, 1993
Surveyor's Michigan License No. 28429