

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

94 DEC 14 AM 9:40

Filing Requirement of Act 74, Mich. P.A. 1970

Randy J. Vugteveen
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in OTTAWA

(County)

Located In:

Corner Code #

- | | | | | | |
|---------------------------------------|---|----|---|-----|--|
| 1. Public Land Survey | T | 6N | R | 13W | E-9 (SE cor of
Sec 20)
Georgetown Twp. |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous
Property in Sec. | S | | T | R | |
| | S | | T | R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, Randal J. Vugteveen, in a field survey on November 22, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
E-9 common corner to Sections 20, 21, 28 & 29

1831 - Lyon & Sibley	Liber 2, Page 443
Tamrack 8" is corner	Centerline 30" Oak S85 $\frac{1}{2}$ E 144.8'
No witnesses	8" C. Elm N80 $\frac{1}{2}$ W 69.13'
	Trp 8" W Ch N10 $\frac{1}{2}$ E 168.60'
	E-W fence S 2'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-9 Found 3/4" pipe with 3 rocks around it at N edge of open field 285' E of N-S ditch and accepted as a careful and faithful perpetuation of the position of the original corner

Centerline 30" Oak S85 $\frac{1}{2}$ E 144.8'	
8" C. Elm N80 $\frac{1}{2}$ W 68.58'	
Triple 8" W. Cherry N101 $\frac{1}{2}$ E 168.60'	
E-W fence S 2'	

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Murray D. McDowell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-9 Drove 3/4" X 36" solid bar in 3/4" pipe & Set Ottawa County Remon Cap

Set Ottawa County Tag & Nail in S side 36" oak S87E 144.68'
Set Ottawa County Tag & Nail in S side Elm stump N88W 68.68'
Set Ottawa County Tag & Nail in S side Triple 12" Elm N55W 156.30'
Set Ottawa County Tag & Nail in S side Triple 12" Wild Cherry N8E 167.91'



Signed by *Randal J. Vugteveen*
Surveyor's Michigan License No. 28429

Date Dec 12, 1994