

FEB 24 2000

RECORDED

OTTAWA COUNTY REMONUMENTATION

99 DEC -2 PM 1:13

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Gary Schellert
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

OTTAWA

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 6N R 13W E-12 W 1/4 corner
 T R Section 33
 T R Georgetown Twp
 T R _____
- 2. Property Controlling S T R _____
 in Section S T R _____
- 3. Miscellaneous S T R _____
 Property in Sec. S T R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randal J. Vugteveen, in a field survey on October 6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-12 G.L.O. August 1831 Lucius Lyon D.S.

Set hard wood post

3" B. Walnut N86°E 29 Links

20" B. Walnut N32°W 32 Links

E-12 Liber 2, Page 241

Exxel May, 1973

R.R. Spike

Nail in side P. Pole WNW 52.00'

Nail in side T. Pole NE 58.49'

Nail in side light pole SE 70.54'

E-12 Liber 2, Page 243 (W & W, July 1973)

RR Spike

V cut SW corner Bridge Pilaster N55°E 16.7'

V cut NE corner bridge Pilaster S35°W 18.95'

V cut NE corner bridge Pilaster N70°W 15.65'

(Continued on Back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12 Found 1/2" Round iron pipe (Top leaning South)

On centerline North & South road and in line with centerline of road to East

Pickett fence to West North 1.5'

Found "X" cut in sidewalk N90°W 33.00'

Found Nail on E side Telephone Pole N30°E 76.91'

Accepting 1/2" Round Iron Pipe as a careful and faithful perpetuation of the position of the original corner.

Replaced 1/2" Round Iron Pipe with a 3/4" X 24" solid bar with Ottawa County Remon Cap in Monument Box

11/15/99
YDN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12 3/4" X 24" solid bar with Ottawa County Remon Cap in Monument box

Set Nail and Remon Tag in S side Power Pole N90°W 45.36'

Set Nail and Remon Tag in E side Telephone Pole N30°E 76.91'

Set Nail and Remon Tag in N side Power Pole N85°E 104.94'

Set Nail and Remon Tag in NE side light pole S42°E 51.28'

On centerline "X" of roads



\$11.00 CORNER
Receipt #64945

Signed by *Randal J. Vugteveen*

Date OCTOBER 27 1999

Surveyor's Michigan License No. 28429

FEB 24 2000

SECTION

A. Continued

E-12 Liber 2, Page 759 March 1975

½" Pipe in centerline of road is in line with property fence to West and centerline road to the East. Fits highway ties.

Telephone Pole & Street Light S30°E 70.55'

Power Pole N65°W 51.84'

Telephone Pole N30°E 76.93'