

RECORDED

FEB 24 2000

OTTAWA COUNTY REMONUMENTATION 99 DEC -2 PM 1:12

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Gary Scholtz
REGISTER OF DEEDS
OTTAWA COUNTY, MICH.

SECTION
For corners in
OTTAWA
(County)

Located In:	Corner Code #
T 6N R 13W	E-13, SW Cor
T R	Section 33,
T R	Georgetown Twp
T R	
S T R	
S T R	
S T R	
S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal J. Vugteveen, in a field survey on October 6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13 Set by GLO
1831 Lucious Lyon
Set Post
14" Sugar N65°E 34 Links
5" Beech N79°W 28 Links

E-13 LCRC Liber 1, Page 191
June 1971 W & W
Found BT Spk by using Ottawa County Witness Map
SW corner hse N50°W 107.60'
Centerline hydrant N35°W 41.50'
CP Pole S70°W 58.00'
MBT Pole N30°E 51.80'

E-13 LCRC #501
June 1973 W & W
1" Iron
NW corner porch found S35°E 63.40'
SW corner house found N45°E 91.94'
SE corner house found N25°W 72.26'
(This is incorrect label, witness fit F-12 Georgetown)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 Found 1/2" Rebar 1.5' East of Centerline "X" of road

SE corner brick house N55°W 107.49'
(Note: Call for SE hse cor in Liber 1, Page 191 was mislabeled as SW hse corner)
Center of hydrant N43°W 42.98'

Accepted 1/2" Rebar as a careful and faithful perpetuation of the position of the original corner.

Removed 1/2" Rebar and replaced with a 3/4" X 24" solid bar with Ottawa County Remon Cap in Monument Box

APPROVED 11/15/99
YDN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 3/4" X 24" solid bar with Ottawa County Remon Cap in Monument Box

Set Nail & Remon Tag in N'y side P. Pole S50°E 47.48'
Set Nail & Remon Tag in SE side P. Pole N42°E 46.22'
Set Nail & Remon Tag in SW side signal pole N49°W 47.86'
Set Nail & Remon Tag in North side of Power Pole S57°W 57.49'
On centerline E & W road 1.5' East of N & S Road



49.00 CORNER
Receipt #64945

Signed by *Randal J. Vugteveen*
Surveyor's Michigan License No. 28429

Date OCTOBER 27, 1999