

DEC 01 1998

SECTION

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa

(County)

Located In: Georgetown Township

Corner Code #/

1. Public Land Survey	T	6N	R	13W	F-1
	T		R		N 1/4 Cor.
	T		R		Sec. 4
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

RECORDED

98 JUL 24 PM 1:46

*Lang*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Rodney D. Unema, in a field survey on June 19, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F-1  
Corner not set by G.L.O.  
L.C.R.C., Liber 5, Page 227  
September, 1985 Exxel  
Set rerod & Exxel cap  
Nail in E side 8" Elm South 24.54'  
Nail in SE sde 10" Elm SW 3.85'  
Nail in NE sde 12" Ash NW 5.92'  
Nail in NW sde 3" Maple NE 11.55'  
Nail in SW sde 14" Ash SE 39.20'  
Tru-Line Survey - 11/6/96  
Capped rerod  
Nail in SE sde 9" dead tree - SW 3.87'  
Nail & tag in SW sde 8" Ash - SE 5.77'  
Nail & tag in SE sde 6" Ash - NE 14.12'  
Nail & tag in NE sde 13" Ash - NNW 5.92'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 Found Capped Exxel Iron \*Over for sketch  
Found nail & tag in SW side 12" Ash S45°E 5.78'  
Found nail in E'ly side 10" Elm (dead) S50°W 3.89'  
Found nail & tag in E side 6" Ash (dead) N54°E 14.06'

This position not established by original government surveyors  
This monument is accepted as the best available evidence of the position of the corner.

Replaced capped re-rod with standard Ottawa Co. Cap on 3/4" X 36" Steel Bar on South line of ~~Tallmadge~~ Township (T7N, R13W)

PA. 345 OTTAWA COUNTY  
PEER APPROVED 7-20-98  
*R.D.U.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 N 1/4 Corner, Section 4  
Ottawa Co. Cap on 3/4" X 36" Steel Bar  
Set nail & O.C. tag in SW side 10" Maple S24°E 26.09'  
Set nail & O.C. tag in N side 12" Ash S45°E 5.64'  
Set nail & O.C. tag in NE side 16" Ash N46°W 5.95'  
Set nail & O.C. tag in N side 14" Ash N90°E 24.00'  
¢ of gravel road West 185 feet  
F-13, T7N, R13W West 31.41'



Signed by Rodney D. Unema  
Surveyor's Michigan License No. 33987

Date June 30, 1998

SURVEY &  
REMONUMENTATION

DEC 01 1998

SECTION

G. LENGEMANN CO. NS2327

SEC. 33-7-13

