

APR 05 1996

OTTAWA COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
OTTAWA
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|-------------------------|----------------------------|
| 1. Public Land Survey | T6N R13W | F-7 (S 1/4 cor Section 16) |
| | T _____ R _____ | Georgetown Twp. |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED

95 NOV 15 PM 2:13

Ruthie Bellman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Randal J. Vugteveen, in a field survey on October 11, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2		
3											
4	7		8		9		10		11		
5											
6	18		17		16		15		14		
7											
8	19		20		21		22		23		
9											
10	30		29		28		27		26		
11											
12	31		32		33		34		35		
13											

A. Description of original monument and accessories and/or subsequent restoration:

F-7 Common corner to Sections 16 & 21

1831 - Sibley	Liber 3, Page 33	Liber 1, Page 743
Beech 101 Links is corner	PK nail in S side of pp N85W 31.66'	Nail in side pp SE 69.6'
	Boat spike in N side of 15" Oak S05E	Nail in side PP WNW 31.6'
	72.70'	Spike in side 12" Maple E 72.77'
	PK nail in E side of pp S35E 69.60'	NE cor hse fndn NW 99.91'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7 Found 3/4" in mon box on centerline 28th Ave 168' S of centerline Sun Valley St. and accepted as a careful and faithful perpetuation of the position of the original corner
PK nail in S side of PP N85W 31.63'
PK nail in SW side of p. pole Az 139 deg 69.59'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 10/23/95
Randal J. Vugteveen
RDJ

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7 Removed 3/4" rod, set 3/4" x 24" solid bar with Ottawa County Remon cap in mon box

NW foundation corner garage #7192 28th Az. 100 deg 95.34'
SE brick corner garage #7293 28th Az. 223 deg 106.78'
NE block foundation corner house #7303 28th Az. 313 deg 99.90'
Centerline Sun Valley Street North 168'



Signed by *Randal J. Vugteveen*
Surveyor's Michigan License No. 28429

Date Oct. 20, 1995