

**SURVEY & REMONUMENTATION**

APR 24 1995

**COMMISSION**

For corners in OTTAWA

OTTAWA COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:41

*Dorothy K. Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>13W</u>	F-9 (S 1/4 cor of Section 21) Georgetown Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randal J. Vugteveen, in a field survey on December 7, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
F-9 Common corner to Section 21 & 28

1831 - Lyon & Sibley	Liber 1, Page 203 & 204
Maple 10" is corner	SW corner house fndn N30W 37.93'
No witnesses	SE cor hse centerline fndn N10E 20.60'
	NW cor bank S40W 82.30'
	10" Maple S50W 20.37'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
F-9 Found concrete mon 20.6' South of House #6498 Balsam Dr. & 110' E of centerline Balsam Drive and accepted as a careful and faithful perpetuation of the position of the original corner


SW corner house fndn N30W 37.93'
SE cor hse centerline fndn N10E 20.60'
10" Maple S50W 20.34'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94

*Murray P. Newell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
F-9 Removed concrete mon, set 3/4" x 36" solid bar with Ottawa County Remon Cap

AZ = Michigan State Grid Direction  
Set Ottawa County Remon Tag & Nail in E side 24" Maple AZ. 228 deg 20.34'  
SE foundation corner house #6498 (not garage) AZ. 19 deg 20.60'  
Set Ottawa County Remon Tag & Nail in SE side 36" Oak AZ. 80 deg 36.82'  
Set Ottawa County Remon Tag & Nail in S side 12" Elm AZ. 143 deg 53.87'



Signed by *Randal J. Vugteveen*  
Surveyor's Michigan License No. 28429

Date Dec 9, 1994