

**SURVEY & REMONUMENTATION**

JUN 28 1999

RECORDED

OTTAWA COUNTY REMONUMENTATION 98 NOV 11 PM 1:25

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*[Signature]*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

**SECTION**

For corners in

| OTTAWA<br>(County)                 | Located In:              | Corner Code #   |
|------------------------------------|--------------------------|---|
| 1. Public Land Survey              | T <u>6N</u> R <u>13W</u> | <u>F-13 S 1/4 cor Sec</u><br><u>33 Georgetown Twp</u> |
|                                    | T ___ R ___              | _____   |
|                                    | T ___ R ___              | _____   |
|                                    | T ___ R ___              | _____   |
| 2. Property Controlling in Section | S ___ T ___ R ___        | _____   |
|                                    | S ___ T ___ R ___        | _____   |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___        | _____   |
|                                    | S ___ T ___ R ___        | _____   |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randal J. Vugteveen, in a field survey on October 12, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 19 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

GLO January 1832  
Lucious Lyon D.S.  
Set Hardwood Post  
18" Beech N56°E 31 Links  
4" Beech N74°1/2°W 40 Links

Liber 2 Page 383  
Bonnema 1975  
T" Iron  
20" Maple SE 50.09'  
23" Cherry SE 23.68'  
18" Maple SSW 21.87'  
22" Maple SW 50.55'

A.v. Peck 1886  
NW corner Section 4-5-13 to N 1/4 cor Sec 4-5-13  
40.11 Chains = 2647.25'  
(Common Corners)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Bar with Remon Cap in Mon Box

Found 1/2" Bar & Cap (Nederveid Associates)  
S33.11'  
Apparent occupation line to the North 0' West


Monument is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 10/19/98  
*[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Bar with Ottawa County Remon Cap in Mon Box

SE corner Brick House Az 339° 70.89'  
SW corner Brick House Az 12° 65.73'  
SE corner Brick House Az 48° 94.19'  
Found Nail and Ottawa Co. Remon tag NE side 18" Maple Az 126° 101.87'  
Found Nail and Ottawa Co. Remon tag W side 24" Beech Az 186° 66.96' on centerline E & W B.T. Road  
Corner is Common to F-1 Jamestown Twp.



\$9.00 CORNER  
Receipt #19293

Signed by *[Signature]*  
Surveyor's Michigan License No. 28429

Date OCTOBER 19, 1998