

APR 05 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
OTTAWA
(County)

	Located In:	Corner Code #/
1. Public Land Survey	T6N R13W	G-8 (E 1/4 cor Section 21) Georgetown Twp.
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED

95 NOV 15 PM 2:13

R. J. Vugteveen
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randal J. Vugteveen, in a field survey on October 11, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-8 Common corner to Sections 21 & 22

1831 - Sibley	Liber 1, Page 207
Set HMP	N3E 10.93' nail in face of 6" Oak
Pine S8 E28 10 Links	N85E 34.92' nail in face of triple 22" W Cherry
Pine N22 W19 30 Links	S85W 16.70' nail in face of 10" Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 Found concrete mon at chain link fence corner N.W.S. and accepted as a careful and faithful perpetuation of the position of the original corner
Found nail E side 12" Oak 11.27'

P.A. 345 OTTAWA COUNTY


PEER APPROVED 10/23/95

Kudoy D. Nedwold
NOV

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 Removed conc mon, set 3/4" x 36" solid bar with Ottawa County Remon cap

Set Ottawa County Remon Nail & Tag in E side 12" Quad Oak Az. 5 deg 11.26'
Set Ottawa County Remon Nail & Tag in N side Twin 18" oak Az. 265 deg 17.18'
Set Ottawa County Remon Nail & Tag in N side 24" Triple W. Cherry Az. 85 deg 37.48'
Face 3" solid steel fence post Az. 225 deg 0.25'



Signed by Randal J. Vugteveen
Surveyor's Michigan License No. 28429

Date Oct. 20, 1995