

**SURVEY & REMONUMENTATION**

APR 24 1995

**COMMISSION**

OTTAWA COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:41

*Register of Deeds*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in OTTAWA

(County)

Located In:

Corner Code #

- |                                    |                          |  |
|------------------------------------|--------------------------|--|
| 1. Public Land Survey              | T <u>6N</u> R <u>13W</u> | G-11 (SE cor of Sec 28)<br>Georgetown Twp. |
|                                    | T _____ R _____          | _____                                      |
|                                    | T _____ R _____          | _____                                      |
|                                    | T _____ R _____          | _____                                      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____                                      |
|                                    | S _____ T _____ R _____  | _____                                      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____                                      |
|                                    | S _____ T _____ R _____  | _____                                      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randal J. Vugteveen, in a field survey on November 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G-11 common corner to Sections 27, 28, 33 & 34	Liber 1, Pages 205 & 206	Liber 1, Page 749
1831 - Lyon & Sibley	NE cor hse S40°W 82.15'	NE cor hse SW 79.1'
16" Birch is corner	NW cor hse S50°W 105.92'	NW cor hse SE 115.6'
No witnesses	CP Pole N60°E 49.83'	
	MBT Pole S60°E 71.25'	

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G-11 Found boat spike in mon box 0.5' S of centerline Van Buren St. treeline N & S and accepted as a careful and faithful perpetuation of the position of the original corner

NE corner house SW 79.1'	NE cor hse AZ 220 82.24'
	NW cor hse AZ 230 105.78'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94  
*Rudolf P. Nedewald*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-11 Removed boat spike, set 3/4" X 24" solid bar with Ottawa County Remon Cap in mon box


AZ = Michigan State Grid Direction

NE corner brick foundation porch house #2414 AZ. 213 deg 80.58'

NW foundation corner garage #2390 AZ. 144 deg 84.88'

Set Ottawa County Remon Tag & Nail in S side P. pole AZ. 60 deg 50.50'

Set Ottawa County Remon Tag & Nail in W side 40" Male AZ. 13 deg 61.20'



Signed by *Randal J. Vugteveen*  
Surveyor's Michigan License No. 28429

Date Dec 9, 1994