

SURVEY & REMONUMENTATION

DEC 01 1993

OTTAWA COUNTY REMONUMENTATION

RECORDED

93 NOV 11 AM 11:53

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

D. J. Bellman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in OTTAWA

(County)

Located In: Corner Code #

1. Public Land Survey	T	6N	R	13W	H-7 (S 1/4 cor Section 15) Georgetown Twp
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randal J. Vugteven, in a field survey on August 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
H-7 Common 1/4 corner to Sections 15 & 22


LCRC Liber 1, Page 115	LCRC Liber 1, Page 473	LCRC Liber 1, Page 731
Iron Pipe	3/4" pipe in centerline blacktop	3/4" iron in Bit Punt
P. Pole East 36.71'	24" W Cherry N42W 41.8'	20" W Cherry n46W 41.36'
20" Twin Maple SW 48.66'	Twin 24" Maple S65W 48.67'	26" Maple S68W 48.70'
NE cor hse #7207 SW 89.16'	MBT Pole N75E 36.69'	MBT Pole N73W 36.73'
20" Cherry NW 41.38'	Solid 1/2" Iron West 26.78'	
SE cor hse #7223 NW 102.56'		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-7 Found capped iron on centerline 20th Ave and accepted as a careful and faithful perpetuation of the position of the original corner

NE cor hse foundation #7207 89.23'
SE cor hse #7223 102.80'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-7 Set Ottawa County Remon cap on 24" X 3/4" solid iron cemented in bit.

Monument Box 1.5' North
Set Ottawa County Remon Tag & Nail in P. Pole West 24.54'
Set Ottawa County Remon Tag & Nail in N side 24" Twin Maple S70W 49.59'
Set Ottawa County Remon Tag & Nail in W side P. Pole S10E 121.95'
NW brick corner hse #7194 S76E 106.26'
SW brick chimney corner hse #1990 N55E 87.46'



Signed by Randal J. Vugteven

Date Nov 5, 1993

Surveyor's Michigan License No. 28429

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983