

**SURVEY & REMONUMENTATION**

APR 24 1995

COMMISSION

For corners in OTTAWA

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:41

*Deborah L. Williams*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>13W</u>	H-11 (S 1/4 cor of Sec 27) Georgetown Twp.
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randal J. Vugteveen, in a field survey on November 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1831 - Lyon & Sibley Set post	Liber 1, Page 749 Power Pole N 49.62'	Liber 5, Page 92 6" Maple NW 71.25'
B. Ash 14" S35W 37 Links	NE cor hse foundation SW 79.73'	Power Pole N 50.00'
W. Ash 12" N8E 26 Links		Tele. Pole S 30.74'
		NE cor porch SW 83.58'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
H-11 Found CIM in mon box 0.5' South of centerline Van Buren and accepted as a careful and faithful perpetuation of the position of the original corner

NE cor hse foundation SW 79.70'	Nail in E face 14" Maple S 43.59'
	Nail in W face PP N 50.06'
	NE corner conc porch SW 83.50'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94  
*Randal J. Vugteveen*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
H-11 Cast Iron Monument in mon box

AZ = Michigan State Grid Direction  
Set Ottawa County Remon Tag & Nail in W side P. Pole AZ. 180 deg 30.86'  
NE corner foundation house #2030 AZ. 230 deg 79.70'  
Set Ottawa County Remon Tag & Nail in E side P. pole AZ. 0 deg 50.06'  
SE corner foundation house #2007 AZ. 50 deg 128.92'



Signed by *Randal J. Vugteveen*

Date Dec. 12, 1994

Surveyor's Michigan License No. 28429