

**SURVEY & REMONUMENTATION**

DEC 01 1998

**SECTION**

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Ottawa

	(County)	Located In:	Corner Code #
		Georgetown Township	
1. Public Land Survey		T 6N R 13W	I-1
		T _____ R _____	NW Cor.
		T _____ R _____	Sec. 2
		T 7N R 13W	I-13
2. Property Controlling in Section	S _____	T _____ R _____	
	S _____	T _____ R _____	
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	
	S _____	T _____ R _____	

**RECORDED**  
98 JUL 24 PM 1:46

*Ray Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Rodney D. Unema, in a field survey on May 21, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-1 Common corner with I-13, T7N R13W per G.L.O. notes & map. Nov. 1831 Post 6" Hickory N48°E 16 Links 7" Hickory N58°W 20 Links	L.C.R.C., Liber 2, Page 213 June, 1973 - Vankooten Found iron Spike in Tw. 14" Elm W 19.60' Spike in 16" Elm E 34.07' Spike in 8" Hickory NE 7.36' Spike in 6" Oak SW 5.85'	Ottawa Co. Road Comm. Wits. Iron Spike in 12" Elm E 30.25' Spike in 6" Ash NE 7.8' Spike in 18" Elm SE 33.8' Spike in 6" Hickory NE 8.1' Spike in 12" Elm NE 30.4'
--	---	---

(OVER)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-1  
Found 3/4" Iron Pipe on Peninsula of land  
No remaining witnesses were found due to earth work and landscaping etc. around corner. Location of corner checks within 0.2' of position measured in 1977 and 1979 in Sec. 2-6-13 and Sec. 35-7-13 by Exxel Engineering.

Accepted as a careful and faithful perpetuation of the position of the original corner, and replaced 3/4" Iron with standard Ottawa County cap on 3/4" X 36" steel bar.

PA. 345 OTTAWA COUNTY  
PEER APPROVED

6-1-98  
*G.D.P.*

\*Over for sketch

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-1 Ottawa County Cap on 3/4" Steel Bar Set Nail & O.C. tag in E side 14" Ash Set Nail & O.C. tag in NE side 12" Ash Set Nail & O.C. tag in S side 12" Oak Set Nail & O.C. tag in W side 6" Cottonwood Water's edge Water's edge	N10°W 39.26' N40°W 19.46' N90°W 35.12' S0°E 19.45' East 5' S55°W 34'
---	---

Corner is common with I-13, T7N, R13W



Signed by Rodney D. Unema Date May 29, 1998

Surveyor's Michigan License No. 33987

**SURVEY &  
REMONUMENTATION**

DEC 01 1998

**SECTION**

Act 132 Survey  
Exxel Engineering, Inc., May, 1977

3/4" Iron			
Spike in Face Twin 16" Elm	E	34.07'	
Spike in side Twin 6" Ash	NE	7.38'	
Spike in side Twin 12" Oak	SW	58.52'	
Spike in side Twin 14" Oak	S	47.09'	

