## SURVEY & REMONUMENTATION

## OTTAWA COUNTY REMONUMENTATION

OCT 07 1996

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

-							
	r	$\sim$	$\sim$	7	$\neg$	***	~
~(	i~	ŧ.,		R	1 1	34	11
٠,		v	$\sim$	11	w	<u>_</u>	L

For corne®@MMISSI OTTAWA	ON
-----------------------------	----

96 AUG 26 PM 2: 02 Located In: Corner Code ## I-5 (SE corner Section 10) Physica alderna T6N R13W 1. Public Land Survey REGISTER OF DEEDS OTTAWA COUNTY, MI T \_\_\_\_\_ R \_\_\_\_\_ Georgetown Twp \_ R R \_\_\_ R \_ 2. Property Controlling \_ R \_ in Section Miscellaneous Register of Deeds Stamp & File Number Property in Sec. \_\_\_ , Recorded Plat \_\_\_ 4. Lot No. ... 5. Private Claims \_ , in a field survey on October 19 Randal J. Vugteveen 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below: NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate. Description of original monument and accessories and/or subsequent restoration: I-5 Common corner to Sections 10, 11, 14 & 15 1960 - County Surveyor 1831 - Sibley | \$ 33′ to 24″ Elm Set post | N 75 deg E to wit Y in 10" Elm W. Oak N82 W25 14 Links Pine S66 E28 7 Links Fences to W, S, E & N B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: I-5 Found conc mon (broken top) 55' SW of Broadview Dr centerline 142' SE of Ronson Ave and accepted as a careful and faithful perpetuation of the position of the original corner This corner was a plat corner monument and Found conc. mon N 29.65' | has been held for numerous plats including Found Nail in S side 12" Oak East 19' | Broadview Gardens - Broadview Gardens No. | Found Nail in E side 28" Oak South 33' P.A. 345 OTTAWA COUNTY s 331 321 Dak

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-5 Removed conc mon, set 3/4" X 36" solid bar with Ottawa County Remon cap

Set Ottawa County Remon Nail & Tag in N side 12" Oak East 18.74'
Set Ottawa County Remon Nail & Tag in E side 32" Oak South 33.07'
Set Ottawa County Remon Nail & Tag in S side 14" Elm West 9.78'
NE corner garage #8000 Ronson S80W 19.35'
NW brick corner garage #1574 Broadview Dr. S30E 62.14'

Signed by Lawlad J. Tyles
Surveyor's Michigan License No. 28429

VUGTEVEEN
NO.
28429
OLAND SURVEY

ME OF MICA OF

RANDAL

Date **VEC 11, 199** 

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28.
REVISED MAY 14.
REVISED JAN.