SURVEY & REMONUMENTATION

APR 0 5 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
95 NOV 15 PM 2:13
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

For corners in OTTAWA (County)

		Located In:	Corner Code ##
1. Public Land Survey		T6N R13W	I-8 (E 1/4 cor
		T ___ R ___	Section 22)
		T ___ R ___	Georgetown Twp.
		T ___ R ___	
2. Property Controlling	S ___	T ___ R ___	
in Section	S ___	T ___ R ___	
3. Miscellaneous	S ___	T ___ R ___	
Property in Sec.	S ___	T ___ R ___	

4. Lot No. _____ , Recorded Plat _____
5. Private Claims _____



I, Randal J. Vugteveen, in a field survey on October 11, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-8 Common corner to Sections 22 & 23
1831 - Sibley
Set HMP
Lynn S31 W21 8 Links
Beech N30 E29 6 Links

Liber 3, page 259
PK in NW side PP NE 6.97'
PK in E side TP SSE 56.62'
PK in S side PP W 143.52'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8 Found 6" conc Triangle mon 33' N of centerline RR tracks and accepted as a careful and faithful perpetuation of the position of the original corner
PK in E side t. pole Az 157 deg 56.54'
PK in S side p. pole Az 229 deg 151.91'
S side sawed off p. pole 148.80'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 10/23/95
Kendon D. Nedewald
GDN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8 Set 3/4" x 24" solid bar with Ottawa County Remon cap

Face of 3" dia. steel fence post Az. 75 deg 0.65'
Set Ottawa County Remon Nail & Tag in RR tie centerline tracks Az. 160 deg 32.77'
Set Ottawa County Remon Nail & Tag in E side p. pole Az. 167 deg 56.49'
Set Ottawa County Remon Nail & Tag in S side p. pole Az. 229 deg 152.19'
SW corner 16X20 block building Az. 53 deg 158.19'

STATE OF MICHIGAN
RANDAL J. VUGTEVEEN
NO. 28429
LICENSED LAND SURVEYOR

Signed by Randal J. Vugteveen Date Oct 20, 1995
Surveyor's Michigan License No. 28429

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 2
REVISED MAY 1
REVISED JAN