OTTAWA COUNTY REMONUMENTATION

APR 0 5 1996

LAND CORNER RECORDATION CERTIFICATE

CO	AA	AA	100	0	<i>~</i>	h t
	IV.	IVI		\supset	u	N

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

OTTAWA		Located In:	Corner Code ##	95 NOV 15 PM 2: 10	
		Localed III.	Corner Code 44		
1.	Public Land Survey	76N R13W T R T R	I-13 (SE corner Section 34) Georgetown Twp.	REGISTER OF DEEDS OTTAWA COUNTY. MI	
		· T R			
2.	Property Controlling	S T R			
	in Section	S T R			
3.	Miscellaneous	S T R		Register of Deeds Stamp & File Number	

Property in Sec. _ , Recorded Plat _

0.001 = 40	OF
Randal J. Vugteveen , in a field survey on October 19	, 19 _ 72 ,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the	corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules the	refore as required in the
current manual of survey instructions of the United States Department of the	Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points me	ntioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surv	eyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented	d, recovered, found as

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

I-13 Common corner to Sections 34 & 35

1831 - Sibley Set post Sugar N45 W13 16 Links Beech N54 E7 8 Links

expressed below:

5. Private Claims ___

Liber 2, page 529

| "T" iron

PK in side pp NNW 51.86'

| Nail in side 8" Ash NW 48.33'

] 3/4" iron E 16.48' on tree line to N

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: I-13 Found "T" iron 7' North of centerline gravel Jackson St. and accepted as a careful and faithful perpetuation of the position of the original corner

"T" Iron / PK in side p. pole NNW 51.86' / Found Nail & B.C. SW side dead 10" Ash AZ 308 deg NW 48.34' / 3/4" iron E 16.44' on | tree line to N

PA. 345 OTTAWA COUNTY

10

PEER APPROVED 10/23/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Removed "T" iron, set 3/4" X 36" solid bar with Ottawa County Remon Cap 6" below gravel road

Found MVK capped iron Az. 0 deg 32.94' Found 3/4" iron pipe (Jamestown corner) Az. 90 deg 16.44' Found N & J capped iron Az. 155 deg 36.67' Set Ottawa County Remon Nail & Tag E side p. pole Az. 347 deg 51.80' Set chisled "X" in NE corner conc driveway Az. 234 deg 59.96'

Set Ottawa County Remon Wail & Tag in S side 10" #sh Az. 64 deg 41.98'

Signed by Surveyor's Michigan License No. __

ATE OF MICK, TON RANDAL VUGTEVEEN NO. COLAND SUR

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28 REVISED MAY 14