

SURVEY & REMONUMENTATION

OCT 07 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in OTTAWA
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>13W</u>	K-4 (E 1/4 cor Section 11) Georgetown Twp.
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

RECORDED

96 AUG 26 PM 2: 02

Doris C. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal J. Vugteveen, in a field survey on January 4, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-4 Common corner to Sections 11 & 12

1832 - Sibley	Liber 5, page 41
Set HMP	Capped MVK iron W 61.16'
Pine S50 E19 7 Links	Spike in N side 18" W Cherry E 71.43'
W. Oak N40 W42 34 Links	Spike in SW side 38" Oak S55 E 44.82'
	Spike in E side Tw 20" Oak S 53.69'
	Spike in N side 6" pine S80 W 55.08'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4 Found PK in E edge bit of Wallinwood Drive and accepted as a careful and faithful perpetuation of the position of the original corner


Spike in N side 18" W Cherry E 71.35'
Spike in E side TW 20" Oak S53.65'

P.A. 1345 OTTAWA COUNTY
PEER APPROVED 2-19-96
Jordan P. Medewell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 Removed PK set 24" x 3/4" solid bar with Ottawa County Remon cap

Set Ottawa County Remon Nail & Tag on N side 12" Spruce AZ 215 deg 96.55'
Set Ottawa County Remon Nail & Tag on E side Twin 20" Oak Az. 183 deg 53.65'
Set Ottawa County Remon Nail & Tag on N side 18" Cherry Az. 97 deg 71.35'
Top Centerline hydrant Az. 332 deg 75.75'



Signed by *[Signature]*

Date FEB 19, 1996

Surveyor's Michigan License No. 28429