

**SURVEY &
REMONUMENTATION**

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:39

Richard B. Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in OTTAWA

(County)

Located In:

Corner Code #

- | | | | | | |
|---------------------------------------|---|----|---|-----|---|
| 1. Public Land Survey | T | 6N | R | 13W | K-8 (E 1/4 cor
of Sec 23)
Georgetown Twp. |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous
Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Randal J. Vugteveen, in a field survey on November 29, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-8 common corner to Sections 23 & 24


- | | | |
|-------------------------|--------------------|-------------------------|
| 1831 - Lyon & Sibley | Liber 3, Page 140 | Liber 3, Page 156 |
| H.M. corner in stream | Conc mon N 99.34' | 36" Elm N 7.18' |
| B. Ash 6" S75E 12 Links | Conc mon NW 64.67' | 16" Basswood ENE 28.47' |
| B. Ash 19" N3W 87 Links | Lot iron S 185.0' | NE hse cor WSW 134.24' |

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-8 Found concrete mon 3' East of garage in back yard house #6786 Ashbury Ct. and accepted as a careful and faithful perpetuation of the position of the original corner
36" Elm N 7.18' | Lot iron S 184.7'
NE house cor WSW 134.24'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Randal J. Vugteveen

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-8 Removed concrete mon, set 3/4" X 36" solid bar with Ottawa County Remon Cap

- AZ = Michigan State Grid Direction
Set Ottawa County Remon Tag & Nail in W side 36" Maple AZ. 0 deg 6.86'
Block foundation to garage AZ. 270 deg 3.17'
Set Ottawa County Remon Tag & Nail in N side 20" Basswood AZ. 84 deg 50.77'
SE foundation corner garage AZ. 195 deg 9.24'



Signed by *Randal J. Vugteveen* Date Dec 12, 1994
Surveyor's Michigan License No. 28429

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983