

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:43

Randy K. Redwood
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in OTTAWA

(County)

Located In:

Corner Code #

| | | | | | |
|------------------------------------|---|----|---|-----|-----------------|
| 1. Public Land Survey | T | 6N | R | 13W | K-10 (E 1/4 cor |
| | T | | R | | Section 26) |
| | T | | R | | Georgetown Twp |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | |
| | S | | T | | |
| 3. Miscellaneous Property in Sec. | S | | T | | |
| | S | | T | | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

Randal J. Vugteveen, in a field survey on December 6, 1994, to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-10 Common corner to Sections 25 & 26

| | |
|-------------------------|---|
| 1831 - Lyon & Sibley | Liber 2, Page 391 |
| Set H.M.P. | Boat Spike |
| Beech 10" N45E 27 Links | Centerline B.T. West 2.3' |
| Sugar 6" S58W 19 Links | Nail in side P. Pole NW 62.36' |
| | Nail in side Triple 12" Box Elder SSW 113.72' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-10 Found boat spike in mon box 3.4' East of centerline 8th Avenue and accepted as a careful and faithful perpetuation of the position of the original corner


| |
|---|
| Centerline B.T. West 3.4' |
| Nail in side P. pole NW 62.32' |
| Nail in side Triple 12" Box Elder SSW 113.72' |

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Randy K. Redwood

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-10 Removed boat spike, set 3/4" X 36" solid bar with Ottawa County Remon Cap

- AZ = Michigan State Grid Direction
- Set Ottawa County Remon Tag & Nail in E side Triple 14" Box Elder AZ. 194 deg 112.93'
- Top Hydrant AZ. 153 deg 60.09'
- Set Ottawa County Remon Tag & Nail in NW side 14" Maple AZ. 31 deg 46.69'
- Set Ottawa County Remon Tag & Nail in S side P. pole AZ. 313 deg 62.32'



Signed by *Randal J. Vugteveen*

Date DEC 9, 1994

Surveyor's Michigan License No. 28429