

SURVEY & REMONUMENTATION

FEB 27 1998

OTTAWA COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in OTTAWA

	Located In:	Corner Code #/	
(County)	6N 13W	L-5 (S 1/4 cor of	
1. Public Land Survey	T _____ R _____	Sec. 12)	
	T _____ R _____	Georgetown Twp.	
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

RECORDED

97 DEC -8 AM 11:30

Larry Schultz
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Randal J. Vugteveen, in a field survey on August 19, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-5 common corner to Sections 12 & 13
1831 - Sibley
Set 1/4 Section Post
Maple 12S 60W 25 Links
Elm 12N 51E 31 Links

Liber 5, Page 141
Spike in Wly side 28" Sycamore S12E 69.19' / Spike in Nly side Triple 10" Ash S72E 11.78' / Spike in NE side 22" Ash N60W 36.41' / Spike in Ely side 12" Ash N22E 11.09' / E-W fence South 115.5' / SW edge Grand River East 259'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5 Found Exxel Cap and accepted as a careful and faithful perpetuation of the original corner.

Found spike in Wly side 28" Sycamore S12E 69.17' / Found Spike in Nly side Triple 12" Ash S72E 11.72' / Found Spike in NE side 22" Ash N60W 36.41' / Found spike in Ely side 12" Ash N22E 11.05' / E-W fence South 120' / SW edge Grand River East 259'


P.A. 345 OTTAWA COUNTY
PEER APPROVED 8-20-96

YDN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 Removed Exxel Cap set 3/4 X 36" solid bar with Ottawa County Remon Cap

Set Ottawa County Remon Nail & Tag in Westerly side 28" Sycamore S12E 69.17'
Set Ottawa County Remon Nail & Tag in Northely side Triple 12" Ash S72E 11.72'
Set Ottawa County Remon Nail & Tag in NE side 22" Ash N60W 36.41'
Set Ottawa County Remon Nail & Tag in Easterly side 12" Ash N22E 11.05'



7.5W UNRCA
\$ 1.00 PHOTO

Signed by *Randal J. Vugteveen*
Surveyor's Michigan License No. 28429

Date August 20, 1996