

APR 05 1996

Ottawa County Remonumentation

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

95 DEC 12 PM 4:52

For corners in

Ottawa (County) Located In: Corner Code ≠#

1. Public Land Survey	T <u>T6N</u> R <u>R13W</u>	<u>M-1</u>
	T _____ R _____	_____
	T _____ R _____	<u>Common corner</u>
	T _____ R _____	<u>w/ M-13</u>
2. Property Controlling in Section	S _____ T _____ R _____	<u>Tallmadge Twp</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Philip H. Whitman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

Maurice J. Rosema in a field survey on March 21, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-1

GLO - in 1837 by R. Clark, Jr. 16" W. Oak N29°E 34 lks. 20" W. Oak S69½°W 70 lks.	L.C.R.C. recorded in Liber 6, page 83 - Jan. 28, 1991 (over)(rec. as M-13, T7N, R13W) L.C.R.C. recorded in Liber 4, Page 292 - Jan. 12, 1982 (over)	L.C.R.C. recorded as #5507 - June 6, 1990 (over)(rec. as A-13, T7N, R12W) L.C.R.C. recorded as #1146 - Feb. 4, 1981 (over)(rec. as A-1, T6N, R12W)
---	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1

Found C.I. mon. 0.2' below bit. conc. road	
Found nail and K.C. tag in E side T pole	N28°W 67.54'
Found nail and K.C. tag in SE side 17" Hackberry	N35°E 40.97'
Found nail and K.C. tag in W side 18" Hackberry	S10°E 72.20'
Found nail and K.C. tag in W side P pole	S80°W 31.24'

P.A. 345 OTTAWA COUNTY

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

PEER APPROVED 12/11/95

*Kendrick D. Newbold*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1

C.I. mon.	
Found nail and K.C. tag in E side T pole	N28°W 67.54'
Found nail and K.C. tag in SE side 17" Hackberry	N35°E 40.97'
Found nail and K.C. tag in W side 18" Hackberry	S10°E 72.20'
Found nail and K.C. tag in N side P pole	S80°W 31.24'
Center stop sign	N47°E 38.25'
Centerline of bit. conc. road N-S	W 7'
Centerline of bit. conc. road to E	N 10'



Signed by *Maurice J. Rosema* Date Dec. 9, 1995

Surveyor's Michigan License No. 27459