

SURVEY & REMONUMENTATION

OCT 07 1996

OTTAWA COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
OTTAWA
(County)

	Located In:	Corner Code #/	
1. Public Land Survey	T <u>6N</u> R <u>13W</u>	M-8 (E 1/4 cor of Sec 24)	<u>Georgetown Twp.</u>
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

RECORDED
96 AUG 26 PM 2:02
Ryszard K. Redwood
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randal J. Vugteveen, in a field survey on December 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-8 common corner to Section 24

1831 - Lyon Sibley Set H.M.P. Beech 24" S78W 35 Links Do 6" N14W 44 Links	Liber 1, Page 471 MSHD nail & tag in centerline CP & MBT pole N87½W 23.70' / Nail & tag in centerline MBT pole S10½W 131.56' / SW cor hse fnd N89½E 113.10'	Liber _____, Page 342 NE cor brick hse @ ground S80½W 126.41' / KC mon S 17.08' (A-8, 6-12) / NE cor 5' conc walk S50½E 46.70' / Nail & KC Remon tag in SE side 8" Pine N30½E 101.70' / SW cor brick hse @ ground N70½E 110.91' / PK nail S & E 2.00'
--	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-8 Found capped iron in bit on centerline Kenowa and accepted as a careful and faithful perpetuation of the position of the original corner


MSHD nail & tag in C/L CP & MBT pole N87½W 27.44' / SW cor hse fnd N89½E 113.0'	NE cor brick hse @ ground S80½W 122.47' / KC mon S 17.98' (A-8, 6-12) / Nail & KC Remon tag in SE side 8" Pine N30½E 101.69' / SW cor brick hse @ ground AZ 77 110.88'
--	--

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/11/95

Ryszard K. Redwood

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-8 Set 24" x 3/4" solid bar with Ottawa County Remon Cap in mon box

- NE corner brick house #6805 AZ 253 126.31'
- Kent County monument AZ 180 17.97'
- NW corner 16" X 16" brick light pier AZ 130 98.02'
- SW corner brick house #3966 AZ 83 113.00'
- SW corner brick house #3966 AZ 77 110.88'



Signed by *Randal J. Vugteveen*
Surveyor's Michigan License No. 28429

Date Dec 11, 1995