

# SURVEY & REMONUMENTATION

APR 24 1995

## COMMISSION

For corners in OTTAWA

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:40

*Register of Deeds*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> , R <u>13W</u>	M-11 (SE cor Section 25) Georgetown Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randal J. Vugteveen, in a field survey on December 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-11 Common corner to Sections 25 & 26	Liber 3, Page 299
1831 - Lyon & Sibley	1" Iron
Set post	MSHD Nail & tag in side T. pole E 25.22'
Beech 10" S381/2W 46 Links	PK in side P. pole SE 66.00'
Do 7" N10W 18 Links	Nail & tag in side 12" Maple NW 25.90'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
M-11 Found Kent County Remon C1M T6N, R12W, stamped A-11 1.7' West of centerline Kenowa on fence line to West and accepted as a careful and faithful perpetuation of the position of the original corner

PK in side P. pole SE 66.00'	
Nail & Tag in N side 12" Ash NW 25.82'	

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94  
*Meredith D. Nedwell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M-11 Cast Iron Monument in Mon Box

AZ = Michigan State Grid Direction  
Set Ottawa County Remon Tag & Nail in N side 18" Ash AZ. 300 deg 25.73'  
Top hydrant AZ. 27 deg 64.94'  
Set Ottawa County Remon Tag & Nail in SW side P. pole AZ. 149 deg 66.00'  
Set Ottawa County Remon Tag & Nail in NW side 14" Pine AZ. 241 deg 46.36'

Signed by Randal J. Vugteveen Date Dec 9, 1994  
Surveyor's Michigan License No. 28429