

FEB 24 2000

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
99 SEP -9 PM 12: 15

SECTION

For corners in

Ottawa (County)	Located In: Blendon Twp.	Corner Code # A-10 W 1/4 Cor Sec. 30
1. Public Land Survey	6N 14W T___ R___ T___ R___ T___ R___ T___ R___	_____ _____ _____ _____
2. Property Controlling in Section	S___ T___ R___ S___ T___ R___	_____ _____
3. Miscellaneous Property in Sec.	S___ T___ R___ S___ T___ R___	_____ _____

Dan Sullivan
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Randal D. Feenstra

Feb. 23 99

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.	L-1, P-353, 1972 (Clapp)	L-2, P-101, 1973 (Exxel)
Not Set	A-10 Found brass plug	A-10 Found 1" brass plug in concrete
	Nail in face of Power Pole SE 102.85'	TKA nail in Power Pole SE 102.83'
	Nail in Face of Telephone Pole SW 43.91'	TKA nail in Side Telephone Pole SW 43.92'
	Nail in Face of 30" Maple NE 47.90'	"X" in concrete S 64.68'
	SW House Corner NE 94.96'	SW corner house foundation NE 94.97'
	Chiseled "X" in Centerline of pavement (Olive corner) S 64.69	Centerline concrete pavement E 25'
		On line with centerline gravel to East (Continued on other side)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10 Found: Cast Iron Monument in monument box	0.07' E of Olive Twp. Line
Nail N. Side of Power Pole	AZ 51°0' 65.67'
Nail N. Side of Power Pole	AZ 150°30' 102.96'
Cast Iron Monument in monument box (Olive Cor.)	S 64.55'

This position not established by original government surveyors. This location is accepted as the best available evidence of the position of the corner.

PA. 345 1/27/99
FIELD APPROVED 8/30/99



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10 Cast Iron Monument in monument box (See Sketch)		
Set Ottawa County Remon Nail & Tag in NW side of Power Pole	AZ 51°0'	65.67'
Set Ottawa County Remon Nail & Tag in NE side of Power Pole	AZ 150°30'	102.96'
Set Ottawa County Remon Nail & Tag in E side of Power Pole	AZ 228°10'	39.64'
Set Ottawa County Remon Nail & Tag in SE side 10" Mult. Maple	AZ 198°35'	152.71'
Cast Iron Monument in monument box (Olive corner)	South 64.55'	
Centerline N-S bituminous road (96th Ave.)	East 0.2'	
Centerline Gravel road to E (Bingham St.)	South 4.0'	
Centerline Gravel road to W (Bingham St.)	South 64.0'	

\$11.00 CORNER
Receipt #56820
\$2.00 PHOTO
Receipt #56820

Signed by

Randal D. Feenstra

Surveyor's Michigan License No. 37275

Date May 14, 1999

FEB 24 2000

SECTION

L-6, P-13, 1989 (Joiner)

A-10 Cast Iron Monument

PK Nail in N side of Power Pole

Nail in N side of Power Pole

PK nail in S side of Telephone Pole

Nail in W side of 18" Maple

E 1/4 Cor, Sec. 25-6-15

S30°E 103.05

N50°E 65.94

N65°W 86.75

N15°E 81.00

S 64.67'

