

**SURVEY & REMONUMENTATION**

APR 05 1996

**COMMISSION**

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Ottawa  
(County)

Located In:  
Blendon Twp.

Corner Code #

1. Public Land Survey	T	6N	R	14W	C-13, SW Cor.
	T		R		Sec. 32
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

**RECORDED**

95 NOV 29 PM 1:43

*Randy D. Fenstra*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randal D. Fenstra, in a field survey on Nov. 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1832)	LIBER 1, PAGE 661 (1972)	LIBER 4, PAGE 284 (1981)
Calvin Britain	"T" Iron	C.I.M.
4" Maple N21°E 18 lks.	T. Pole NE 47.62'	T. Pole NW 86.08'
10" Maple N64°W 27 lks.	Guard Rail Post SE 16.25'	T. Pole SW 79.15'
	"X" in SW cor., conc. culv. SW 61.75'	Zeeland cor. W. 46.73'
	Stone W 46.30'	Nail in guard rail post SE 16.77'
	(Zeeland cor.)	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: C.I.M. Accepted as a careful and faithful perpetuation of the position of the original corner.  
Zeeland Twp. Corner (C.I.M.) 46.70' (W.)

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11/20/95  
*Randy D. Fenstra*  
RDF

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13	C.I.M. in gravel		
	NW cor. 4.5' x 5' steel lid to MichCon M.H.	38°	39.34'
	Ottawa County Remon. Nail and Tag in E side P. Pole	352°	203.14'
	Dept. of Interior Brass Plate in W headwall of E-W culv.	247°	53.78'
	Zeeland Township Corner (C.I.M.)	272°	46.70'



Signed by *Randal D. Fenstra*  
Surveyor's Michigan License No. 37275

Date Nov. 6, 1995