

SURVEY & REMONUMENTATION

OCT 24 1994

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

91 OCT -7 PM 12:33

Ralph A. Callman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa
(County)

Located In:

Corner Code #

1. Public Land Survey	T 6N	R 14W	F-3, Nor 1/4 COR
	T	R	Sec. 9, Blendon
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal D. Feenstra, in a field survey on May 9, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L.O. (1932)	Liber 2, Pg. 239 (1973)	Liber 3, PG. 368 (1979)	Liber 5, Pg. 2 (1982)
Tamarack N60°E 1.0	RR Spike	RR Spike	C.I.M.
Tamarack S15°E 128.7	PP	SE Cor, SE conc.	"X" on Hdwl. NE 38.12
OST	TP	wing wall	"X" on Hdwl. NNW 42.12
Paul Marrs	TP	SE 42.88	PP NW 88.14
		PP NW 88.09	PP SE 42.94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: Cast Iron Monument in Mon. Box - accepted as a careful and faithful perpetuation of the position of the original corner.

Found Witnesses:

Pk. Nail NE side MBT support post	S40°E 42.98
Nail & cap SE side PP	N65°W 87.72

P.A. 345 OTTAWA COUNTY

PEER APPROVED 9/22/04

Randal D. Feenstra

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3 Cast Iron Mon.	
O.C. Remon. Nail & tag top of 24" CMP culvert	S45°W 39.36
O.C. Remon. Nail & tag W side MBT support post	S40°E 42.90
O.C. Remon. Nail & tag S side PP	N65°W 88.02
Chisled "X" in S edge of conc. culvert	N30°E 40.65
1.5' N of Taylor Road CL and 1.0' W of 76th CL	



Signed by Randal D. Feenstra Date May 9, 1994

Surveyor's Michigan License No. 37275