

SURVEY & REMONUMENTATION

OCT 24 1994

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 OCT -7 PM 12:34

R. K. Kellman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|------------|-----------------|
| 1. Public Land Survey | T 6N R 14W | I-4W1/4 COR |
| | T R | Sec. 11 Blendon |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

Randal D. Feenstra, in a field survey on May 26, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

31.0 (1838))	Liber 1, Page 755 (1972)	Liber 5, Page 117 (1984)
18" Black Ash N24°E 9.2	IRON	C.I.M.
18" Black Ash S24° 6.6	CL Bit. Conc. N 1.0	12" Pine NW 34.10
POST	NW Cor. Hse. Fndn. SSE 85.77	4" Tree NE 64.48
Samuel Marrs	NE Cor. Hse. SE 100.24	PP S 35.45
	PP N 67.13	14" Maple SE 72.59
	PP S 35.40	

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: C.I.M. in Monument Box - accepted as a careful and faithful perpetuation of the found position of the original corner.

- Found Witnesses:
- Pk in W side PP S05°E 35.81
 - Nail in N side PP S05°E 35.89
 - Nail in E side 12" Pine N25°W 34.10

P.A. 345 OTTAWA COUNTY
PEER APPROVED 8/22/94

Randal D. Feenstra

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-4 Cast Iron Monument
- O.C. Remon. Nail & tag E side PP S05°E 35.41
- O.C. Remon. Nail & tag E side 12" Pine N25°W 33.89'
- O.C. Remon. Nail & tag W side 6" Elm N35°E 60.71'
- O.C. Remon. Nail & tag NE side 24" Maple S45°E 72.35'
- CL Bauer Road



Signed by Randal D. Feenstra

Date May 26, 1994

Surveyor's Michigan License No. 37275