

**SURVEY & REMONUMENTATION**

APR 05 1996

**COMMISSION**

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Ottawa

(County)

Located In:

Corner Code #

1. Public Land Survey	Blendon Twp.			I-6, E 1/4 cor. Sec. 15
	T	6N	R 14W	
	T		R	
	T		R	
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

RECORDED

95 NOV 29 PM 1:43

*D. J. ...*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randal D. Feenstra, in a field survey on November 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

C.I.M. (1832) Calvin Britain 18" Maple N75°E 11 lks. 6" Birch S64°W 8 lks.	LIBER 2, PAGE 705 (1974) 3/4" Iron Spike in 14" Pipe SW 80.73' Nail in 12" Oak NW 74.16' Nail in 10" Maple NNW 56.24'	LIBER 2, PAGE 757 (1975) 1" Pipe St. Sign SW 33.73' Post SE 54.26' 8" Maple NNW 56.06'	LIBER 4, PAGE 256 (1981) C.I.M. 5" Pepperidge NE 56.40' 12" Maple N 56.13' 12" Oak NW 74.03' 16" Pine SW 80.50'
---	---	--	--

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found: C.I.M. Accepted as a careful and faithful perpetuation of the position of the original corner.

Nail and Cap in NW side 20" Pine SW 80.50'  
Nail in SW side 14" Oak NW 74.03'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11/20/95

*M. D. ...*  
*R D D*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-6 C.I.M. in gravel		
Ottawa County Remon. Nail & Tag in W side 14" Maple	38°	72.51'
Ottawa County Remon. Nail & Tag in SW side 12" Oak	320°	73.91'
Ottawa County Remon. Nail & Tag in W side P. Pole	160°	101.40'
Ottawa County Remon. Nail & Tag in NW side 20" Pine	220°	80.38'

5' W of centerline "X" Baldwin St. and 64th Ave.



Signed by Randal D. Feenstra

Date November 6, 1995

Surveyor's Michigan License No. 37275