

SURVEY & REMONUMENTATION

OCT 24 1994

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 OCT -7 PH 12: 33

Rudolph A. Redman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 14W	I-9, SE COR Sec. 22, Blendon
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Randal D. Feenstra, in a field survey on May 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

.L.O. (1832)	Liber 1, Page 761 (1972)	Liber 5, Page 120 (1984)
OST		
0" Birch N61°E 4.0'	Iron in Mon. Box	C.I.M.
~ Elm S37°W 10.6'	Nail in P.Pole SW 40.24	P.P. SW 40.36
Samuel Marrs	Nail in 36" Oak NNW 55.10	G.P. NW 43.15
	Nail in P.Pole NW 42.98	32" Tree NNW 105.62
	Nail in P.Pole NE 172.31	Gas Pipeline Sign NE 53.60

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: Cast Iron Monument in Monument Box - accepted as a careful and faithful perpetuation of the position of the original corner.

Found Witnesses:

Spike in NW side PP	SW 40.35'
Nail in PP	NE 172.10'
Spike in E side 48" Oak	NNW 106.72'


PA. 345 OTTAWA COUNTY

PEER APPROVED 8/22/94

Gordon P. Hedewell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 Cast Iron Mon. in Monument box	
O.C. Remon. Nail & Tag in NW side PP	S45°W 40.23'
O.C. Remon. Nail & Tag in W side PP	S45°E 45.69'
O.C. Remon. Nail & Tag in SW side post	
by MBT Ped.	N45°W 43.02'
O.C. Remon. Nail & Tag in SW side 40" Oak	N25°W 105.88'



Signed by Randal D. Feenstra

Date May 4, 1994

Surveyor's Michigan License No. 37275